Machine Translated by Google
RCMOS - Multidisciplinary Scientific Journal The Knowledge.
ISSN: 2675-9128. São Paulo-SP.

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

The integration of artificial intelligence into the BIM methodology for managing highly complex civil engineering projects.

The integration of artificial intelligence and BIM methodology in high-complexity civil construction management

The integration of artificial intelligence with the BIM methodology in the management of highly complex civil works

Francisco Machado da Silveira Neto [1]

SUMMARY

This article analyzes in depth the impact of the convergence between artificial intelligence tools and Building Information Modeling (BIM) methodology on the management of large-scale residential and commercial projects. The investigation addresses the transition from static planning models to dynamic predictive systems, focusing on the automated detection of structural incompatibilities and the optimization of...

Budgetary resources. The study discusses how the automation of critical processes mitigates the occurrence of cost overruns and schedule delays in highly complex construction projects.

The results indicate that integrated computer simulation substantially increases operational predictability and efficiency in the allocation of construction inputs. It is concluded that advanced simulation and data processing consolidate digital engineering as an indispensable pillar of contemporary construction.

Keywords: Artificial Intelligence; BIM Methodology; Construction Management; Digital Engineering; Operational Predictability.

ABSTRACT

This article provides an in-depth analysis of the impact of the convergence of artificial intelligence tools and Building Information Modeling (BIM) methodology on the management of large-scale residential and commercial projects. The investigation addresses the transition from static planning models to dynamic predictive systems, focusing on the automated detection of structural incompatibilities and the optimization of budgetary resources. The study discusses how critical process automation mitigates cost overruns and schedule delays at high-complexity construction sites. The results indicate that integrated computer simulation substantially increases operational predictability and efficiency in allocating construction resources. It concludes that advanced simulation and data processing consolidate digital engineering as an indispensable pillar of contemporary construction.

Keywords: Artificial Intelligence; BIM Methodology; Construction Management; Digital Engineering; Operational Predictability.

1. INTRODUCTION

The construction sector plays a crucial role in macroeconomic development.

globally, the industry is primarily responsible for generating millions of direct jobs and for...

[1] Civil Engineer (Roseira College); Building Technician (Curso Nobre Technical School); Real Estate Transactions Technician (EDUQ Technical School). Specialist in Project Management and Large-Scale Construction.

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google
RCMOS – Multidisciplinary Scientific Journal The Knowledge.
ISSN: 2675-9128. São Paulo-SP.

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

Consolidation of urban infrastructure for entire nations. However, the management of large-scale projects.
Historically, it has faced severe structural challenges, such as budget overruns and...
Failure to meet physical schedules. The inherent complexity of projects.
Contemporary tasks demand a level of coordination that often exceeds the capabilities of modern people.
of traditional control methods based on spreadsheets and manual checks
field.
Over the last two decades, the introduction of the Building Information Modeling (BIM) methodology
It implemented the first major structural digital transformation in the construction sector. This technology
It replaced traditional two-dimensional drawing with loaded three-dimensional digital models.
of complex parametric data. The BIM model functions, in practice, as a database of
A unified dataset that brings together geometric and technical information from all disciplines of...
undertaking. Despite its undeniable efficiency in visual coordination, BIM,
Even in isolation, it still demands a significant amount of human analysis for decision-making.
complex predictive technologies in real time.
In this context of accelerated technological transition, artificial intelligence emerges as the
The ultimate tool capable of enhancing BIM model data. The application of
Machine learning and neural network algorithms applied to constructive data enable...
anticipation of execution failures and automated optimization of sequencing.
daily activities. The central objective of this article is to investigate how the integration of these two
Technological forces are redefining the governance of highly complex civil engineering projects and acting...
directly mitigating the invisible risks that increase the final cost of projects.

2. METHODOLOGY

This research was conducted based on a high-quality systematic literature review.
academic rigor. The analysis included the construction of conceptual scenarios based on
Practical application of advanced digital technologies in contemporary civil engineering. The search
Based on theoretical frameworks, it focused strictly on scientific articles indexed in...
major global databases and guidelines from international regulatory bodies
construction. The sample scope prioritized recent publications that directly discussed the
use of predictive algorithms coupled with intelligent three-dimensional modeling platforms
of buildings.
The methodological analysis was structured around the meticulous categorization of the dimensions of

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

BIM (3D modeling, 4D planning, and 5D budgeting). The study evaluated the optimization of each dimension through different branches of artificial intelligence, encompassing the Intensive use of computer vision and natural language processing on the construction site. Qualitative data extracted from the literature were cross-referenced with performance indicators. Widely validated in engineering project management.

The methodological rigor sought to ensure the complete reproducibility of the theoretical premises. discussed in this research. A clear analytical line was established that connects the Mathematical foundations of computational algorithms to operational routines experienced daily on large construction sites. The triangulation of literary sources aimed to eliminate individual interpretative biases and consolidate an irrefutable technical overview on The current state of the art in augmented civil engineering.

3. The BIM Model as a Parametric Database

Understanding BIM as an integrated information ecosystem represents the starting point. A dogmatic departure from the norm for modernizing construction processes. The model should be... seen as much more than a simple software for visual representation of architecture. Each An object inserted into a three-dimensional model carries a deep matrix of properties that It rigorously defines its physical, mechanical, and financial nature. This parametric characteristic ensures that the virtual building behaves exactly the same as the physical building. physical counterpart.

A reinforced concrete beam, modeled in a BIM environment, perfectly illustrates the depth of the stored data. The element does not act merely as a visual polyhedron. Located in the building's virtual space. It is an object that contains embedded data. Regarding the characteristic strength of the material, the exact volume of inputs needed, the weight own and the planned schedule for its concreting. All this information is available for immediate extraction by the construction company's strategic planning team.

This formidable structure of parametric data acts as the ideal fuel for the Training of artificial intelligence algorithms applied to engineering. The models Predictive mathematics requires massive volumes of standardized and clean information to... To make reliable and actionable statistical predictions. BIM organizes structural information. so that the machine can read and interpret, in fractions of a second, the complex relationships. of interdependence between the different parts and disciplines of the building.

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

The international standardization provided by the Industry Foundation Classes (IFC) format
This enables interoperability between different software programs on the market. This open standard guarantees...
that the data flow does not suffer critical interruptions during the transition between project phases.
Architectural, structural calculation, and on-site execution. The universalization of data.
It allows artificial intelligence systems to operate agnostically and analyze models.
complexes regardless of the commercial platform on which they were originally developed.
conceived.

The informational richness of the BIM database also extends to temporal dimensions.
and financial on an ongoing basis. The direct and bidirectional link between the geometry of the project, the
The physical timeline and budget spreadsheets create a robust three-dimensional foundation for the...
Executive governance of the project. The manager abandons reading textual reports.
disconnected and begins to visualize the financial behavior of the project directly integrated.
to the modeled physical space.
Maintaining the absolute integrity of this database throughout its entire lifecycle.
The work proves crucial to the success of any digital engineering initiative. Lapses
Human errors or occasional omissions in filling out the parametric properties generate noise.
computational factors that seriously compromise the accuracy of automated analyses.
subsequent steps. The data governance established in the initial design phase defines the boundary.
operational efficiency that predictive tools can achieve in the execution phase.

4. OPTIMIZATION ALGORITHMS AND COMPUTATIONAL DESIGN

Computational design, combined with generative artificial intelligence, is dramatically transforming the...
The initial process of designing structures and buildings. In the traditional design model.
In project management, the technical team manually tests a fairly limited number of alternatives.
geometric methods to solve a structural problem. This artisanal process, besides being time-consuming,
It depends heavily on the individual intuition of the calculator and often results in solutions
which do not represent the pinnacle of material efficiency.
The systematic introduction of topological optimization algorithms completely reverses this.
Classical operational logic. The civil engineer initially defines all the parameters of
Problem outline, including acting loads, physical space constraints, and standards.
current techniques. From this parametric basis, artificial intelligence explores
automatically, simultaneously and uninterruptedly, thousands of geometric variations

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google
RCMOS - Multidisciplinary Scientific Journal The Knowledge.
ISSN: 2675-9128. São Paulo-SP.

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

possible, seeking the best engineering scenario.

The system exhaustively calculates the mechanical behavior of each spatial alternative.
generated in a virtual environment. After the simulations, the algorithm selects and presents only the
options that aggressively minimize the consumption of construction materials, while maintaining
maintaining the structural rigidity required by safety standards. This ability to
The processing returns mathematically validated options to the engineer that reduce
significantly increases the total cost of foundations and superstructures.

The optimized forms generated by these generative processes often deviate from the...
Traditional orthogonal geometries found in conventional architecture. The elements
Structural elements assume precise organic patterns that mimic biological structures.
complex shapes found in nature. These forms, considered impossible to calculate or to
Drawing manually in a timely manner proves incredibly efficient in dissipating
extreme mechanical stresses.

Generative artificial intelligence also plays a decisive role in distribution.
Internal routing of highly complex building installations. The algorithms calculate the paths.
Shorter and more efficient spatial distances for detailed routing of hydraulic and other piping.
Air conditioning ducts. The processing automatically avoids geometric collisions.
unwanted elements that support the building's critical structure, optimizing the usable space of the
technical ceilings and vertical shafts of the building.

The computational speed achieved by these structural simulations allows the office to...
The project manager can now act with previously unimaginable agility. The engineer is able to assess, in
In a matter of minutes, the direct financial impact of profound design changes.
Architectural. Computational design enhances technical security and acts as a true...
analytical amplifier of the fundamental capabilities of the responsible engineering professional.
for the work.

5. ADVANCED PROJECT COMPATIBILITY AND DETECTION OF INCOMPATIBILITIES

Unintentional physical collisions between sanitary pipes and structural beams are one of the
More costly occurrences on traditional construction sites. Massive rework.
resulting from the late identification of design flaws in the physical execution phase responds
due to an alarming portion of the sector's financial losses. Project compatibility

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google
RCMOS - Multidisciplinary Scientific Journal The Knowledge.
ISSN: 2675-9128. São Paulo-SP.

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

The implementation of BIM methodology has already mitigated part of this historical problem, but... Purely visual inspection still leaves room for human error in intricate designs. Artificial intelligence systems applied to advanced compatibility improve accuracy. from the process to a level of analytical infallibility. The model introduces semantic analyses and deep contextual data that easily surpasses simple geometric interference detection. in the three-dimensional model. The algorithm analyzes the design holistically and distinguishes automatically detects actual collisions of interferences that are considered normatively tolerable.

This semantic differentiation eliminates thousands of false positives that often pollute and to make it impossible to analyze reports generated by conventional fact-checking software. A Artificial intelligence assesses the financial impact of each real-world mismatch detected with The system classifies errors based on the direct cost of resolution on the construction site. potential for time delays that the failure would cause if it went unnoticed by the team technical aspects and reached the concreting phase.

This automated prioritization provides mathematical guidance to the responsible engineering team. The professionals' focus is immediately directed towards the approval of the detailed design plans. to the resolution of spatial problems that represent the greatest and most costly risks to Financial integrity of the project. The workflow for architectural and facility reviews. It acquires fluidity based on solid operational risk metrics, and no longer on scans. random.

The algorithms also analyze the strict technical conformity of the virtual models in relation to to the extensive and complex national regulatory framework. The system performs scans Automated steps in the BIM model to verify minimum safety clearances. Structurally, they strictly comply with the legal requirements of the fire departments and... Municipalities. This preventative digital audit completely eliminates the risk of legal disputes. and administrative injunctions during the public inspection phase.

Intelligent project coordination definitively shifts the role of the construction company from... a reactive and corrective level for an anticipatory technical shielding posture. The cost of Correcting for volumetric interference in the digital model represents a negligible fraction. the cost required to demolish a reinforced concrete structure that has already solidified in the field. Artificial intelligence transforms the virtual environment into the ideal terrain for making mistakes and correcting them without... financial penalties.

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google
RCMOS – Multidisciplinary Scientific Journal The Knowledge.
ISSN: 2675-9128. São Paulo-SP.

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

6. Predictive 4D Planning and Deadline Control

The physical schedule of a large project constitutes a highly dynamic system.
Subject to continuous logistical disruptions. Traditional construction planning,
Based solely on the Critical Path Method (CPM), it suffers from its excessive rigidity.
mathematics. This model operates with static and limited durations that rarely reflect the
complex real variability of productivities measured at outdoor work sites.
When unexpected delays occur in critical initial activities, manual rescheduling is necessary.
Creating a complete timeline of the work becomes a lengthy analytical exercise. The document
It often loses its immediate managerial usefulness and comes to reflect only a wish.
Theoretical principles that no longer reflect the reality on the construction site. The structural integration of intelligence.
Artificial intelligence added to the 4D BIM model definitively eliminates this operational limitation by introducing
Predictive engines with continuous recalculation.
The new systems analyze the vast historical physical progress of the teams' own equipment and
outsourced data is stored on the company's servers. The algorithm quickly cross-references these.
historical data with highly accurate weather forecasts for the following weeks and
with the scheduled logistics supply windows. The result is the precise calculation of
statistical probability of meeting each physical milestone established by the planning.
original executive of the company.
Machine learning tools identify patterns with remarkable accuracy.
Hidden behaviors that often precede major delays. If the speed of
The execution of the perimeter masonry falls for only three consecutive days, the system projects.
The immediate cascading effect of this micro-event on the installed finishing disciplines
months ahead. The project manager receives a detailed situational alert, weeks before the...
Global delays will irreparably contaminate the project's critical path.
This formidable computational anticipation capability enables the instantaneous simulation of
Multiple time recovery scenarios. Faced with an imminent time bottleneck, the
The engineer can consult the system regarding the feasibility of adopting work shifts.
extended. The algorithm processes the strict physical space limitations on the construction site and responds
with clear execution alternatives, always accompanied by their respective elevation curves.
costs associated with the corrective maneuver.

4D planning, supported by predictive models, is transforming the old bar chart schedule.
From a simple bureaucratic artifact into a living corporate navigation panel. Annihilation.

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google
RCMOS – Multidisciplinary Scientific Journal The Knowledge.
ISSN: 2675-9128. São Paulo-SP.

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

The systematic uncertainty regarding deadlines completely stabilizes the monthly cash flow of Construction consortium. The company will now operate shielded from the stringent penalties. monetary compensation stipulated in corporate contracts, solidifying its reputation for excellence. Absolute reliability in the timely delivery of infrastructure and real estate assets.

7. SMART BUDGETING AND 5D BIM

The dreaded widespread budget overrun represents the biggest and most damaging offender of Profitability and business sustainability in the construction industry. The development of Preparing executive budgets using traditional methods requires exhaustive manual data collection. Quantitative data is generated from hundreds of design drawings. This archaic methodological workflow is... severely exposed to primary counting errors and dangerous omissions of services essential, compromising the pricing of the proposal.

The definitive association between the BIM 5D dimension and modern machine learning algorithms. The machine ensures the automated extraction of all inputs directly from the matrix. parametric design. This action dramatically reduces the technical time required for The preparation of robust budget documents, shortening the work week cycle. for just a few hours of processing. The technological system links the digital geometry. directly to public and private cost composition databases, ensuring a matching Perfect value.

Artificial intelligence transcends the elementary arithmetic of adding volumes and areas to incorporate powerful predictive analytics on commodity price fluctuations construction. The models analyze the complex time series of inflation indices of steel and cement sectors, projecting the probable and future cost of structural steel for the The exact months in which the 4D schedule indicates the need for acquisition, optimizing the... Setting up the disbursement flow.

The final consistency of the generated budget is ensured through a meticulous algorithmic audit. The system compares the spreadsheet currently being created with historical cost data. effectively incurred in similar works executed and completed by the construction company in the past. Recent. Any abnormal statistical deviation in the predicted consumption of mortar or cables. Electric vehicles are instantly flagged by the platform's intelligence for necessary maintenance. from the body of senior budget engineers.

Budget simulation, perfectly linked to the spatial model, makes it possible to...

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google
RCMOS – Multidisciplinary Scientific Journal The Knowledge.
ISSN: 2675-9128. São Paulo-SP.

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

Unquestionable implementation of real-time value engineering. Layout modifications.
required by the end customer or adjustments to the specifications of air conditioning systems.
central costs are immediately reflected in the totals for indirect costs, social charges, and...
Taxes associated with the project. The construction company operates with complete confidence regarding its viability.
Economic analysis of the project before mobilizing the first field team.
The budget moves beyond the realm of expectations and subjective risk margins to act as...
A rigorous, dynamic business cash management model. The intelligent tool protects
The deal protects against currency fluctuations and ensures that the construction company's managers base their decisions on...
Their decisions are based solely on highly reliable mathematical probabilities. A
Intelligent budgeting ensures the much-desired financial sustainability over long cycles.
It facilitates real estate development and enables the full execution of highly ambitious projects.

CONCLUSION

A thorough investigation into the structural convergence between intelligence networks.
Artificial intelligence and the ramifications of the BIM methodology reveal that civil digitization has consolidated a
irreversible level of precision. The unconditional merging of a modeled database of
The flawless form and brutal computing power of the algorithms definitively puts an end to...
Cycles of uncertainty in planning. Digital engineering can no longer be seen as a mere...
Technological luxury or a corporate marketing differentiator. Mastering these platforms.
determines the effective, financial, and technical survival of construction companies in the market.
international high standard.
The implementation of these tools directly contributes to the elimination of procedural flaws that
For decades, these indicators anchored the industry's productivity indices. Intelligent matching
It anticipates volumetric errors with crystal clarity, while the generative design algorithm
It seeks and delivers the most economical and secure constructive method within the universe of possibilities.
Spatial. Automatic synchronization between the physical schedule and the material budget.
It also reduces empiricism in the strategic management of large volumes of capital.
spin.
The predictability obtained through iterative simulations protects contractual guarantees.
Construction companies and real estate investors. In a market characterized by profit margins.
Despite reduced and high inflationary pressures, the budgetary protection offered by BIM 5D provides significant advantages.
Intelligent design eliminates the risk of abrupt operational shutdowns resulting from inadequacy.

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

budgetary. Organizations that dominate this processing chain demonstrate a
formidable ability to meet strict contractual deadlines and secure financing at competitive rates.
with considerably more attractive interest rates alongside selective investment funds.
In light of the above, it becomes evident that the mass adoption of these systems reconfigures
The profile entirely required of a professional who leads modern projects. The skill in
The operation of physical construction sites remains vital; however, data literacy and understanding
Advanced system integrations have become cardinal requirements for management.
The engineer acts as an ethical validator, ultimate strategist, and curator of hypercomplex solutions.
generated by the machines.
The irrevocable technical responsibility for the structural integrity and human safety of
The entire constructed complex remains unchanged under the aegis of the Engineering Councils.
Artificial intelligence does not suppress human input and judgment; it provides evidence.
irrefutable evidence to ensure that the technical decision reaches its highest level of excellence and accuracy. A
Close collaboration between the engineer's brain and the algorithm creates a constructive environment.
infinitely safer.
The maturation of specialized systems also suggests a new perspective on management.
Sustainable development of the constructed assets. End-to-end parameterized projects guarantee delivery.
From the coveted digital twins to the operators of facilities at the end of the project's execution. This
The informational legacy will enable predictive management of the building's useful life cycle.
in the coming decades, adding invaluable resale and utility value to the asset.
building and consolidating the sector's commitment to global energy efficiency.
It is observed that the complete digital transition of construction methodologies is the factor.
a determining factor in separating market-leading companies from their competitors in
upcoming economic cycles. Gains in speed, accuracy, and loss reduction drive
the development of infrastructure that the previous model would technically and
financially unable to make it viable. The paradigm shift is already consolidated at the core.
from the largest companies in cutting-edge design and construction.
It is therefore established that the definitive alliance between advanced computer science and the
Classical civil engineering ushers in the most promising phase of global infrastructure. The rigor
Embedded scientific knowledge in daily operations promotes the sustainable improvement of
national and global technical productivity, delivering formidable buildings to society,
strictly controlled and built with the utmost respect for invested capital and impact
urban interventions.

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Machine Translated by Google

Year VI, v.1 2025 | Submission: 09/02/2025 | Accepted: 12/02/2025 | Publication: 15/02/2025

REFERENCES

ABNT. **NBR ISO 19650:** Organization and digitization of information on buildings and civil engineering works using BIM. Rio de Janeiro: Brazilian Association of Technical Standards, 2021.

AZHAR, S. Building Information Modeling: Trends, Benefits, Risks, and Challenges for the AEC Industry. **Leadership and Management in Engineering,** vol. 11, no. 3, p. 241–252, 2011.
EASTMAN, C., et al. **BIM Handbook:** A Guide to Building Information Modeling for Owners, Managers, Designers, Engineers, and Contractors. 3rd ed. New Jersey: John Wiley & Sons, 2018.

MATTOS, AD. **Planning and Control of Works.** 2nd ed. São Paulo: Oficina de Textos, 2019.

PROJECT MANAGEMENT INSTITUTE. **A Guide to the Project Management Body of Knowledge (PMBOK Guide).** 7. ed. Pennsylvania: Project Management Institute, 2021.
RUSSELL, S., NORVIG, P. **Artificial Intelligence:** A Modern Approach. 4th ed. Rio de Janeiro: GEN LTC, 2022.
SACKS, R., et al. **Building Information Modeling:** Framework for Structural Design. New York: Routledge, 2020.
SUCCAR, B. Building information modeling framework: A research and delivery foundation for industry stakeholders. **Automation in Construction,** vol. 18, no. 3, p. 357–375, 2009.

This article is published in open access under the Creative Commons Attribution license, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.